


Erosion Control and Stormwater Quality Guide



Colorado
Department of Transportation - 2002



Acknowledgments

CDOT Environmental Programs

Tom Boyce
Mike Banovich
Cathy Curtis

CDOT Region and Staff Hydraulics

Al Gross
Gil Highland
Stephen Harelson
Amanullah Mommandi
Peter Kozinski

CDOT Construction

Michael Hodgson

CDOT Region Environmental

Steve Sherman

CDOT Hazardous Materials

Andy Flurkey

CDOT Utilities

Rich Horstmann

CH2M HILL

Barbara Chongtoua
Pat Nelson
Monika Stopinski

RMR Consulting

Art Hirsch

Altitude Training Associates

Scott S. Olson
Richard Olson

Contents

1.0 Introduction	1-1
2.0 Stormwater Quality Regulations and Program	2-1
2.1 Water Quality Legislation	2-1
2.2 Colorado Department of Transportation Water Quality Program.....	2-1
2.2.1 Construction Program	2-2
3.0 Pollutant Types and Effects on Receiving Waters	3-1
3.1 Erosion and Sedimentation	3-1
3.1.1 Types of Erosion	3-1
3.1.2 Factors Affecting Erosion	3-1
3.2 Pollutant Types and Sources.....	3-2
3.3 Effects of Receiving Waters.....	3-3
3.4 Highway Runoff	3-3
3.4.1 Factors Affecting Pollutant Types and Concentrations	3-3
3.4.2 Effects of Highway Runoff on Receiving Waters.....	3-6
3.4.3 Procedures to Estimate Impacts on Receiving Waters.....	3-6
3.5 Highway Maintenance Practices	3-7
4.0 Stormwater Management Plan Procedures	4-1
4.1 Overview	4-1
4.2 SWMP Procedures.....	4-2
4.3 Creating a Successful Stormwater Management Plan	4-3
4.4 Levels of SWMP Development.....	4-4
4.4.1 Project Scope	4-4
4.4.2 Field Inspection Review (FIR)	4-5
4.4.3 Final Office Review (FOR).....	4-5
4.5 Construction.....	4-6
4.6 Post-Construction Site Evaluation and Report.....	4-7
4.7 CDPS Permit Deactivation Notification	4-8
4.8 Record Keeping.....	4-8
4.8.1 Site Evaluation Procedure	4-8
4.9 SWMP Title Sheet Requirements.....	4-9
4.10 Resources	4-10
4.11 Method of Measurement for Vegetative Cover.....	4-10
4.11.1 Vegetative Cover	4-10
4.11.2 Documentation	4-10
4.12 Termination of General Permit for Stormwater Discharges Associated with Construction Activity.....	4-11
5.0 Construction Best Management Practices	5-1
5.1 Introduction.....	5-1
5.2 Planning	5-1
5.2.1 Site Assessment.....	5-2

5.2.2 Avoidance and Minimization	5-2
5.2.3 Construction Scheduling and Phasing	5-3
5.2.4 Stormwater Management Plan	5-3
5.2.5 Inspection and Maintenance	5-3
5.3 Elements of Best Management Practices	5-3
5.4 Selection of Controls	5-6
5.5 Erosion Control.....	5-7
EC 1: Seeding.....	5-8
EC 2: Mulching	5-10
EC 3: Mulch Tackifier.....	5-12
EC 4: Soil Binder	5-13
EC 5: Erosion Control Blankets	5-14
EC 6: Turf Reinforcement Mats (TRM).....	5-19
EC 7: Embankment Protector.....	5-22
EC 8: Berm/Diversion	5-26
EC 9: Check Dams	5-29
EC 10: Outlet Protection	5-34
EC 11: Temporary Drainage Swale	5-36
EC 12: Grading Techniques.....	5-37
5.6 Sediment Control.....	5-40
SC 1: Erosion Bale	5-41
SC 2: Erosion Logs	5-44
SC 3: Silt Fence	5-47
SC 4: Storm Drain Inlet Protection	5-52
SC 5: Sediment Trap.....	5-56
SC 6: Sediment Basin.....	5-59
SC 7: Dewatering Structure	5-65
SC 8: Stabilized Construction Entrance.....	5-67
SC 9: Brush Barrier	5-69
SC 10: Gravel Barrier.....	5-71
SC 11: Silt Barrier	5-72
5.7 Materials Handling and Spill Prevention	5-75
MH 1: Stockpile Management	5-76
MH 2: Material Management.....	5-77
MH 3: Material Use	5-79
MH 4: Spill Prevention and Control	5-81
5.8 Waste Management.....	5-85
WM 1: Concrete Waste Management	5-86
WM 2: Solid Waste Management.....	5-89
WM 3: Sanitary and Septic Waste Management	5-91
WM 4: Liquid Waste Management	5-92
WM 5: Hazardous Waste Management	5-94
WM 6: Contaminated Waste Management.....	5-97
5.9 General Pollution Prevention	5-99
GP 1: Dewatering Operations.....	5-100
GP 2: Temporary Stream Crossing.....	5-102
GP 3: Clear Water Diversion.....	5-106

GP 4: Non-Stormwater Discharge Management.....	5-108
GP 5: Wind Erosion Control	5-109
GP 6: Paving Operations	5-110
GP 7: Street Sweeping and Vacuuming.....	5-112
GP 8: Vehicle and Equipment Management.....	5-113
6.0 Post Construction Best Management Practices	6-1
6.1 Introduction.....	6-1
6.2 Planning.....	6-1
6.3 Elements of Post Construction Best Management Practices	6-1
6.4 Selection of Controls	6-2
6.5 Post Construction Best Management Practices Fact Sheets.....	6-3
PC 1: Extended Detention Pond with Micropool.....	6-4
PC 2: Wet Pond	6-6
PC 3: Wet Extended Detention Pond.....	6-8
PC 4: Shallow Wetland	6-10
PC 5: Extended Detention Shallow Wetland	6-12
PC 6: Pond/Wetland System	6-14
PC 7: Pocket Wetland.....	6-16
PC 8: Infiltration Trench	6-18
PC 9: Infiltration Basin.....	6-20
PC 10: Surface Sand Filter	6-22
PC 11: Subsurface Sand Filter	6-24
PC 12: Perimeter Sand Filter	6-26
PC 13: Organic Filter	6-28
PC 14: Pocket Sand Filter.....	6-30
PC 15: Bioretention.....	6-32
PC 16: Dry Swale	6-34
PC 17: Wet Swale	6-36
PC 18: Sheet Flow to Buffers	6-38
PC 19: Catch Basin Inserts	6-40
PC 20: Water Quality Inlet with Oil/Grit Separator	6-42
PC 21: Street Sweeping	6-44
PC 22: Deep Sump Catch Basins	6-45
PC 23: On-line Storage in Storm Drain Network (Vaults)	6-47
PC 24: Porous Pavements.....	6-49
PC 25: Proprietary/Manufactured Systems	6-51

Appendix A SWMP Checklist

Glossary

References

Acronyms

AASHTO	American Association of State Highway and Transportation Officials
ADT	average daily traffic
ASCE	American Society of Civil Engineers
BAT	Best Available Technology
BCT	Best Conventional Technology
BMP	Best Management Practice
BOD	biological oxygen demand
CAD	computer-aided design
CDOT	Colorado Department of Transportation
CDPHE	Colorado Department of Public Health and Environment
CDPS	Colorado Discharge Permit System
CFR	Code of Federal Regulations
CFS	cubic feet per second
CRS	Colorado Revised Statutes
EA	Environmental Assessment
EC	Erosion Control - BMP
EIS	Environmental Impact Statement
EMC	event mean concentration
EPA	U.S. Environmental Protection Agency
FEMA	Federal Emergency Management Administration
FHWA	Federal Highway Administration
FIR	Field Inspection Review
FOR	Final Office Review
GP	General Pollution Prevention - BMP
MH	Materials Handling (and Spill Prevention) - BMP
MS4	municipal separate storm sewer system

MSDS	Material Safety Data Sheet
NEPA	National Environmental Policy Act of 1969
NPDES	National Pollutant Discharge Elimination System
NURP	National Urban Runoff Program
PCB	polychlorinated biphenyls
PCC	Portland Cement Concrete
OSHA	Occupational Safety and Health Administration
RECAT	Regional Erosion Control Advisory Team
ROW	right of way
SC	Sediment Control - BMP
SWMP	Stormwater Management Plan
TRM	turf reinforcement mat
VOC	volatile organic compound
UDFCD	Urban Drainage and Flood Control District
USDOT	U.S. Department of Transportation
UV	ultraviolet
WM	Waste Management - BMP
WQCD	Water Quality Control Division
WQCV	water quality capture volume